





## **CURB INLET SEDIMENT CONTROL**






# PELICAN DRAIN INLET PROTECTION






# FLOW DIVERSION WEIGHTED WATTLE



#### TYPICAL PROTECTION FOR INLET WITH OPPOSING FLOW DIRECTIONS



### TYPICAL PROTECTION FOR INLET WITH SINGLE FLOW DIRECTION

- 1. Intended for short-term use.
- Use to inhibit non-storm water flow.
  Allow for proper maintenance and cleanup.

CHECKED BY

EB/JS

- Bags must be removed after adjacent operation is completed
  Not applicable in areas with high silts and clays without filter fabric.



### **TEMPORARY INLET PROTECTION**

				Ī			
				ĺ			
				l			
				ĺ			
				ĺ			
No.	REVISIONS	DATE	BY	ĺ			



Kimley-Horn and Associates, Inc.

© 2013 KIMLEY-HORN AND ASSOCIATES, INC. 6130 STONERIDGE MALL RD, STE 370 PLEASANTON, CA 94588 PHONE: 925-398-4840 FAX: 925-398-4849 WWW.KIMLEY-HORN.COM



TOOTE ON THE PROPERTY OF THE P	DESIGNED BY	DRAWN BY	CHECK		
Q.C.BIL	EB/JS	KT/BH	EB/		
	PLANS PR	EPARED UNDER SUPER	VISION OF:		
ND. C75125	ERIC BILAND, P.E.				
EMP. 12/31/13	REGISTERED CIVIL ENGINEER				
CIVIL	SEPTEMBER 2013		75125		
1443	DATE		RCE NO.		



# SANITARY SEWER PLANS **BMP DETAILS**

NOTES

1. CURB INLET SEDIMENT CONTROL TO BE USED AT ALL DOWNSTREAM INLETS FROM WORK AREAS.

2. FLOW DIVERSION WEIGHTED WATTLE AND PELICAN DRAIN INLET PROTECTION SHALL BE USED ONLY DURING CONSTRUCTION HOURS. BMPS SHALL BE REMOVED AT THE END OF EACH WORK DAY.

3. SACKED TEMPORARY INLET PROTECTION SHALL BE USED IMMEDIATELY UPSTREAM OF THE NEAREST DOWNSTREAM INLET TO ANY ACTIVE CONSTRUCTION WORK WHERE SAWCUTTING OR DEMOLITION WORK IS IN PROGRESS. LIMITS OF SACKED PROTECTION SHALL BE CONED OFF AT THE END OF EACH WORK DAY.

DRAWING NO SS-07 SHEET 27 of 27 JOB No. 097901001

CITY OF SAUSALITO 2013 STREET IMPROVEMENT PROJECT