

BASE BID

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
1	SITE PREPARATION.					
2	Demolish and remove off site (e):					
3	Gravel/asphalt parking and driveway	27,000	sf			
4	Sod, ground cover, etc.	1	ls			
6	Concrete planter walls	150	lf			
7	Log rails	10	ea			
8	Concrete lattice fencing	225	lf			
9	Gate	1	ea			
10	Bollards	9	ea			
11	Underground utility lines	1	ls			
12	Trees, incl grinding stumps	40	ea			
13	Miscellaneous demolition	1	ls			
14	Temporary fencing	1	ls			
15	Protect (e) trees, etc.	1	ls			
16	Remove, save and reinstall at a later date (e):					
17	Park sign	2	ea			
18	Sign poles	1	ls			
19	Concrete wheel stops	24	ea			
20	Sand (volley ball court)	1	ls			
21	Site Preparation					
22	Clear and grub area of site	80,000	sf			
23	Prep subgrade, scarify, compact	80,000	sf			Balanced cut and fill
24	Prep site to new levels					
25	Cut, store on site for reuse	2,935	cy			
26	Dry, compact (e) fill	267	cy			
27	Finish grading	80,000	sf			
28	Erosion Control					
29	Gravel construction entrance / exit	2,500	sf			
30	Concrete washout	1	ls			
31	Stockpile fence, tarp, etc.	1	ls			
32	Storm inlet protection	5	ea			
33	Wattles, Ertec	240	lf			
34	Silt fence	260	lf			
35	Periodic Street cleaning	5	mth			
36	Velocity check dams	1	ls			
37	Maintenance crew, sand bags, straw bails, tarps, etc.	1	ls			
	SITE PREPARATION - TOTAL					

BASE BID

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
38	SITE UTILITIES					
39	Storm Drainage					
40	Remove (e) storm line	390	lf			
41	Remove (e) storm line mh	3	ea			
42	Plug (e) lines, partial demo	1	ls			
43	Storm drain 6"	450	lf			
44	Storm drain 8"	400	lf			
45	Storm drain 12"	230	lf			
46	Perf drain 4"	1,000	lf			
47	Area drain:					
48	9"	3	ea			
49	12"	1	ea			
50	18"	7	ea			
51	Catch basin	1	ea			
52	Junction box	1	ea			
53	Cleanouts	4	ea			
54	Connect to (e)	1	ea			
55	Misc. accessories, clean up, test	1	ea			
56	Storm Drainage main run					
57	Storm pipe 30"	560	lf			
58	Storm pipe 36"	100	lf			
59	Connect to (e)	1	ls			
60	Manhole (n)	1	ea			
61	Intercept vault 10x18	1	ea			
62	Sediment collector	1	ea			
63	Outfall	1	ls			
64	Misc. accessories, clean up, test	1	ls			
65						
66	Domestic water / irrigation					
67	Water line, 2"	420	lf			
68	Shutoff valve, 2" in box	3	ea			
69	PRV	1	ea			
70	BFP 2"	1	ea			
71	Drinking fountain w/ dog bowl	1	ea			
72	Water meter	MMWD				
73	Thrust blocks	1	ls			
74	Connect to (e) service	2	ea			
75	Misc. accs., clean up	1	ls			

Dunphy Park,
Sausalito, CA

BASE BID

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
76	Water / fire					
77	Fire hydrant	1	ea			
78	Pipe-FP 4" u/g	280	lf			
79	Valve w/box 4"	1	ea			
80	Auto air release assemb.	1	ea			
81	TB	2	ea			
82	Connect to (e) service	1	ea			
83	Misc. valves & accs.	1	ls			
84	Test & clean	1	ls			
85	Sewer					
86	Sewer line, 6" HDPE	230	lf			
87	Sewer line, 4" HDPE	60	lf			
88	Manhole (n)	1	ea			
89	Manhole connect to (e)	1	ea			
90	Cleanouts	1	ea			
91	Connect to bldgs. 4"	1	ea			
92	Barricades/utility protection	1	ls			
93	Misc. accs., clean up	1	ea			
94						
95	SITE UTILITIES - TOTAL					

BASE BID

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
96	PAVING / FLATWORK					
97	Paving:					
98	AC Paving 6" permeable AC, 4"-1/2" rock, 24"-3/4" rock, Geogrid	27,600	sf			
99	Permeable pavers	2,030	sf			
100						
101	Stabilized aggregate paving, Vehicle, 6" base rock, 4" granitcrete	4,360	sf			
102	Stabilized aggregate paving, Pedestrian, 4" base rock, stabilized agg paving	8,500	sf			
103	Curbs					
104	Driveway approach	120	lf			
105	Curb 6"x16"	1,500	lf			
106	Curb Flush 6"	850	lf			
107	Detectable warning strips	1	ls			
108	Striping	1	ls			
109						
110	PAVING / FLATWORK TOTAL					
111	SITE STRUCTURES / FURNISHINGS					
112	Stone veneer wall (Entry Plaza)					
113	Foundation, complete, 2'x6"	68	lf			
114	Concrete wall, concrete, complete	136	sf			
115	Stone facing	136	sf			
116	Stone cap	68	lf			
117						
118	Bocce ball court (3 ea - 60'x10')					
119	Concrete perimeter, 6"x2'	420	lf			
120	Bumpers and headers	420	lf			
121	Cap, 3"x8"	1,260	bf			
122	Court shell fill, agg base	1,800	sf			
123	Trash enclosure					
124	SOG	105	sf			
125	Curb	31	lf			
126	Footing w/ sleeve	1	ea			
127	4"x4" TS Posts	7	ea			
128	Ceder siding	240	sf			
129	Gate, w/ TS, and hardware	2	ea			

BASE BID

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
130	Miscellaneous					
131	Giant timber seat, 19' long	4	ea			
132	Giant timber seat, 25' long	1	ea			
133	Picnic tables	3	ea			
134	Picnic table ADA	3	ea			
135	Bike racks	7	ea			
136	Wheel stops, cedar, 6"x6"	22	ea			
137						
138						
139						
140						
141	SITE STRUCTURES / FURNISHINGS TOTAL					
142						
143	SIGNAGE					
144	Signage					
145						
146						
147						
148	Park rules	1	ls			
149	Regulatory	1	ls			
150	Parking, ADA	1	ls			
151						
152	SIGNAGE TOTAL					
153						
154	PLANTING AND SOIL PREPARATION					
155						
156	Landscape					
157	Import top soil / loam	346	cy			
158	Turf - natural	6,967	sf			
159	Shrub planting	11,690	sf			
160	Trees, 24 box	17	ea			
161	Trees, 36 box	12	ea			
162	Mulch	11,690	sf			
163	120 day Planting Maintenance	1	ls			
164						
165	PLANTING AND SOIL PREPARATION TOTAL					

BASE BID

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
166	IRRIGATION SYSTEM					
167	Complete irrigation system	6,967	sf			
168	@ turf	11,690	sf			
169	@ shrubs	29	ea			
170	@ trees					
171						
172						
173						
174	IRRIGATION SYSTEM TOTAL					
175						
176	ELECTRICAL					
177	Electrical Relocation:					
178	Safe off, crossover, demo (e) primary	1	ls			
179	and secondary power					
180	Electrical Service:					
181	Locate & Intercept (e) service	1	ls			
182	New 100A Panel, complete	1	ls			
183	Conduit, trench, wire - from panel	300	lf			
184	Protect (e) service	1	ls			
185	Conduit / power in trench	100	lf			
186	GFI's	2	ea			
187	Irrigation controllers					
188	Power, conduit and trench	1	ea			
189	Site Lighting:					
190	Luminaire LED - Pole Single	6	ea			
191	Luminaire LED - Pole Double	6	ea			
192	N9 box	16	ea			
193	N30 box	3	ea			
194	PVC lighting runs, trench	600	lf			
195	Conduit w/ pull string 1"	250	lf			
196	Controls	1	ls			
197	Testing, commission, etc.	1	ls			
198	Add Outlets to Gazebo	1	ls			
199	ELECTRICAL TOTAL					
200						
201	SUBTOTAL				\$	

ADDITIVE ALTERNATE #1 - ADDITION OF ROMTEC RESTROOM

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
1	SITE PREPARATION.					Taken w/ base project
2						
3	SITE PREPARATION - TOTAL					Taken w/ base project
4	SITE UTILITIES					Taken w/ base project
5						
6	SITE UTILITIES - TOTAL					Taken w/ base project
7	PAVING / FLATWORK					Taken w/ base project
8						
9	PAVING / FLATWORK TOTAL					Taken w/ base project
10						
11	SITE STRUCTURES / FURNISHINGS					By Owner
12						
13	Restroom, 14'x28'					
14	Pre-Engineered building materials					
15	Off load, store					
16	Slab on grade					
17	CMU wall, install					
18	Roof framing, install					
19	Siding / trim, install					
20	Doors, frames and hardware, install					
21	Metal roof, insulation, etc. install					
22	Paint interior walls, ceiling, doors, exterior siding, trim					
23	Install partitions, etc.					
24	Plumbing rough					
25	Plumbing, install, finish					
26	HVAC					
27	Sprinkler					
28	Electrical rough					
29	Electrical, install, finish					
30	Breakage					
31						
32	SITE STRUCTURES / FURNISHINGS TOTAL					Taken w/ base project
33						\$ -
34	SIGNAGE					
35						
36	SIGNAGE TOTAL					

Dunphy Park,
Sausalito, CA

ADDITIVE ALTERNATE #1 - ADDITION OF ROMTEC RESTROOM

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
37						
38						
39	PLANTING AND SOIL PREPARATION					Taken w/ base project
40	PLANTING AND SOIL PREPARATION TOTAL					
41						
42	IRRIGATION SYSTEM					Taken w/ base project
43						
44	IRRIGATION SYSTEM TOTAL					
45						
46	ELECTRICAL					Taken w/ base project
47						
48	ELECTRICAL TOTAL					
49						
50	SUBTOTAL					

ADDITIVE ALTERNATE #2 - ADDITION OF VOLLEYBALL COURT

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
1	SITE PREPARATION.					
2	Site Preparation					w/ base project
3	Clear and grub area of site					
4	Prep subgrade, scarify, compact	4,640	sf			
5	Prep site to new levels					
6	Cut, store on site for reuse	168	cy			
7	Dry, compact (e) fill	8	cy			
8	Finish grading	4,640	sf			
9						
10	Erosion Control					w/ base project
11						
12	SITE PREPARATION - TOTAL					
13	SITE UTILITIES					w/ base project
14						
15	SITE UTILITIES - TOTAL					
16	PAVING / FLATWORK					w/ base project
17						
18	PAVING / FLATWORK TOTAL					
19						
20	SITE STRUCTURES / FURNISHINGS					
21						
22	Volleyball court (50'x80')					
23						
24						
25	Concrete post base	2	ea			
26	Baserock	74	cy			
27	Sand	259	cy			
28	Post and net	1	ls			
29						
30	SITE STRUCTURES / FURNISHINGS TOTAL					
31						
32	SIGNAGE					w/ base project
33						
34	SIGNAGE TOTAL					
35						
36	PLANTING AND SOIL PREPARATION					w/ base project
37						
38	PLANTING AND SOIL PREPARATION TOTAL					

Dunphy Park,
Sausalito, CA

ADDITIVE ALTERNATE #2 - ADDITION OF VOLLEYBALL COURT

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
39	IRRIGATION SYSTEM					w/ base project
40						
41						
42	IRRIGATION SYSTEM TOTAL					
43	ELECTRICAL					w/ base project
44						
45						
46	ELECTRICAL TOTAL					
47						
48	SUBTOTAL					

ADDITIVE ALTERNATE #3 ADDITION OF CENTRAL PARK AREA

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
0	SITE PREPARATION.					
1	Demolish and remove off site (e):					
2	Asphalt paving	2,800	sf			
3	Bocce courts	2	ea			
4	Timber pilings	7	ea			
5	Storm drain cover	1	ls			
6	Log rails	4	ea			
7	Bollards	8	ea			
8	Sod, ground cover, etc.	1	ls			
9	Underground utility lines	1	ls			
10	Trees, incl grinding stumps	17	ea			
11	Miscellaneous demolition	1	ls			
12	Temporary fencing	1	ls			
13	Protect (e) trees, gazebo, etc.	1	ls			
14	Remove, save and reinstall at a later date (e):					
15	Sign poles	1	ls			
16	Benches	1	ls			
17	Plaques	2	ea			
18	Stone seats	8	ea			
19	Site Preparation					
20	Clear and grub area of site	65,500	sf			
21	Prep subgrade, scarify, compact	65,500	sf			
22	Prep site to new levels					
23	Cut, store on site for reuse	132	cy			Balanced cut and fill
24	Dry, compact (e) fill	2,802	cy			
25	Finish grading	65,500	sf			From base bid area
26	Erosion Control					
27	Gravel construction entrance / exit	2,500	sf			w/ base project
28	Concrete washout	1	ls			w/ base project
29	Stockpile fence, tarp, etc.	1	ls			w/ base project
30	Storm inlet protection	7	ea			
31	Wattles, Ertec	336	lf			
32	Silt fence	480	lf			
33	Periodic Street cleaning	5	mth			
34	Velocity check dams	1	ls			
35	Maintenance crew, sand bags, straw bails, tarps, etc.	1	ls			w/ base project
36	SITE PREPARATION - TOTAL					

ADDITIVE ALTERNATE #3 - ADDITION OF CENTRAL PARK AREA

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
37	SITE UTILITIES					
38						
39	SITE UTILITIES - TOTAL				\$ -	w/ base project
40	PAVING / FLATWORK					
41	Paving:					
42	Stabilized aggregate paving, Pedestrian, 4" base rock, stabilized agg paving	7,140	sf			
43						
44	Curbs					
45	Curb Flush 6"	160	lf			
46						
47	PAVING / FLATWORK TOTAL					
48						
49	SITE STRUCTURES / FURNISHINGS					
50						
51						
52	Miscellaneous					
53	Giant timber seat, 6' long	6	ea			
54	Picnic tables	3	ea			
55	Picnic table ADA	1	ea			
56	Bike racks	3	ea			
57	Wood bollards	3	ea			
58	Trash recycle receptacles	4	ea			
59						
60	Fence, cedar posts, wire mesh, 3'	115	lf			
61						
62	SITE STRUCTURES / FURNISHINGS TOTAL					

ADDITIVE ALTERNATE #3 - ADDITION OF CENTRAL PARK AREA

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
63	SIGNAGE					
64	Signage					
65						
66						
67	Park rules	1				
68	Regulatory	1				
69						
70	SIGNAGE TOTAL					
71						
72						
73						
74	PLANTING AND SOIL PREPARATION					
75	Landscape					
76	Import top soil / loam	1,070	cy			
77	Turf - natural	52,144	sf			
78	Shrub planting	5,619	sf			
79	Trees, 24 box	5	ea			
80	Trees, 36 box	12	ea			
81	Mulch	5,619	sf			
82	120 day Planting Maintenance	1	ls			
83	PLANTING AND SOIL PREPARATION TOTAL					
84						
85	IRRIGATION SYSTEM					
86						
87	Complete irrigation system					
88	@ turf	52,144	sf			
89	@shrubs	5,619	sf			
90	@ trees	17	ea			
91						
92	IRRIGATION SYSTEM TOTAL					

Dunphy Park,
Sausalito, CA

ADDITIVE ALTERNATE #3 - ADDITION OF CENTRAL PARK AREA

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
93	ELECTRICAL					
94	Electrical Relocation:					
95	Safe off, crossover, demo (e) power	1	ls			
96	Electrical Service:					
97	Conduit, trench, wire - from panel	525	lf			
98	Utility boxes	1	ls			
99	Picnic table outlets	2	ea			
100						
101						
102						
103						
104	ELECTRICAL TOTAL					
105						
106	SUBTOTAL					

ADDITIVE ALTERNATE #4 - ADDITION OF SOUTH AND EAST OF LITHO STREET WORK

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
1	SITE PREPARATION.					
2	Demolish and remove off site (e):					
3	Asphalt paving	2,070	sf			
4	Fencing	450	lf			
5	Site Preparation					
6	Clear and grub area of site	28,750	sf			
7	Prep subgrade, scarify, compact	28,750	sf			
8	Prep site to new levels					Balanced cut and fill
9	Cut, store on site for reuse	282	cy			
10	Dry, compact (e) fill	5	cy			
11	Finish grading	28,750	sf			
12						
13	Erosion Control					
14	Gravel construction entrance / exit	2,500	sf			w/ base project
15	Concrete washout	1	ls			w/ base project
16	Stockpile fence, tarp, etc.	1	ls			w/ base project
17	Storm inlet protection	5	ea			
18	Wattles, Ertec	320	lf			
19	Silt fence	400	lf			
20	Periodic Street cleaning	5	mth			
21	Velocity check dams	1	ls			w/ base project
22	Maintenance crew, sand bags, straw bails, tarps, etc.	1	ls			
23						
24	SITE PREPARATION - TOTAL					
25	SITE UTILITIES					None
26	SITE UTILITIES - TOTAL					
27	PAVING / FLATWORK					
28	Paving:					
29	Stabilized aggregate paving,					
	Pedestrian, 4" base rock, stabilized					
	agg paving	2,500	sf			
30						
31						
32	PAVING / FLATWORK TOTAL					

ADDITIVE ALTERNATE #4 - ADDITION OF SOUTH AND EAST OF LITHO STREET WORK

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
33	SITE STRUCTURES / FURNISHINGS					
34						
35						
36	Miscellaneous					
37	Picnic tables	1	ea			
38	Picnic table ADA	1	ea			
39						
40	SITE STRUCTURES / FURNISHINGS TOTAL					
41						
42	SIGNAGE					
43	Signage					
44						
45	Park rules	1	ls			
46	Regulatory	1	ls			
47						
48	SIGNAGE TOTAL					
49						
50						
51	PLANTING AND SOIL PREPARATION					
52						
53	Landscpe					
54	Import top soil / loam	464	cy			
55	Shrub planting	25,060	sf			
56	Trees, 24 box	15	ea			
57	Trees, 36 box	2	ea			
58	Mulch	25,060	sf			
59	120 day Planting Maintenance	1	ls			
60	PLANTING AND SOIL PREPARATION TOTAL					
61						
62	IRRIGATION SYSTEM					
63						
64	Complete irrigation system	25,060	sf			
65	@shrubs	17	ea			
66	@ trees					
67	IRRIGATION SYSTEM TOTAL					
68						

Dunphy Park,
Sausalito, CA

ADDITIVE ALTERNATE #4 - ADDITION OF SOUTH AND EAST LITHO STREET WORK

Line #	Description	Quantity	Unit	rate	cost	Comments / Subtotal.
69	ELECTRICAL					None
70						
71						
72	ELECTRICAL TOTAL					
73						
74	SUBTOTAL					

ADDITIVE ALTERNATE #5 - ADDITION OF SHORELINE BEACH ACCESS WORK

Line #	Description	Quantity	Unit	rate	Est. cost	Comments / Subtotal.
1	SITE PREPARATION.					
2	Demolish and remove off site (e):					
3	Timber pilings	26	ea			
4	Miscellaneous demolition	1	ls			
5	Protect (e) trees, gazebo, etc.	1	ls			
6	Site Preparation					
7	Clear and grub area of site	2,500	sf			Balanced cut and fill
8	Prep subgrade, scarify, compact	2,500	sf			
9	Prep site to new levels					
10	Dry, compact (e) fill	254	cy			
11	Finish grading	2,500	sf			
12						
13	Erosion Control					
14	Gravel construction entrance / exit	2,500	sf			w/ base project
15	Concrete washout	1	ls			w/ base project
16	Stockpile fence, tarp, etc.	1	ls			w/ base project
17	Wattles, Ertec	240	lf			
18	Silt fence	260	lf			
19	Periodic Street cleaning	5	mth			w/ base project
20	Velocity check dams	1	ls			
21	Maintenance crew, sand bags, straw bails, tarps, etc.	1	ls			
22						
23	SITE PREPARATION - TOTAL					
24	SITE UTILITIES					None
25						
26	SITE UTILITIES - TOTAL					
27	PAVING / FLATWORK					None
28						
29	PAVING / FLATWORK TOTAL					

ADDITIVE ALTERNATE #5 - ADDITION OF SHORELINE BEACH ACCESS WORK

Line #	Description	Quantity	Unit	rate	Est. cost	Comments / Subtotal.
30	SITE STRUCTURES / FURNISHINGS					
31						
32						
33	Shoreline Access					
34	Foundation, complete	115	lf			
35	Concrete wall, complete	460	sf			
36	Stone facing	288	sf			
37	Stone cap	115	lf			
38	Terrace seating conc base	600	sf			
39	Terrace seating pavers	600	sf			
40	Ramp w/ granite crete	440	sf			
41	Gravel to beach	51	cy			
42						
43	SITE STRUCTURES / FURNISHINGS TOTAL					
44						
45	SIGNAGE					None
46						
47	SIGNAGE TOTAL					
48						
49						
50						
51	PLANTING AND SOIL PREPARATION					None
52	PLANTING AND SOIL PREPARATION TOTAL					
53						
54						
55	IRRIGATION SYSTEM					None
56	IRRIGATION SYSTEM TOTAL					
57						
58	ELECTRICAL					None
59	ELECTRICAL TOTAL					
60						
61	SUBTOTAL					

ADDITIVE ALTERNATE #6 - ADDITION OF LIVING SHORELINE WORK

Line #	Description	Quantity	Unit	rate	Est. cost	Comments / Subtotal.
1	SITE PREPARATION.					
2	Demolish and remove off site (e):					
3	Site Preparation	24,730	sf			
4	Clear and grub area of site	24,730	sf			
5	Prep subgrade, scarify, compact					
6	Prep site to new levels					
7	Cut, store on site for reuse	639	cy			
8	Dry, compact (e) fill	198	cy			
9	Finish grading	24,730	sf			
10						
11	Erosion Control					
12	Gravel construction entrance / exit	2,500	sf			w/ base project
13	Concrete washout		ls			w/ base project
14	Stockpile fence, tarp, etc.		ls			w/ base project
15	Storm inlet protection		ea			w/ base project
16	Wattles, Ertec	900	lf			
17	Silt fence	900	lf			
18	Periodic Street cleaning		mth			
19	Velocity check dams	1	ls			w/ base project
20	Maintenance crew, sand bags, straw bails, tarps, etc.	1	ls			
21						
22	SITE PREPARATION - TOTAL					
23	SITE UTILITIES					None
24						
25	SITE UTILITIES - TOTAL					
26	PAVING / FLATWORK					
27	Paving:					
28	Stabilized aggregate paving,					
	Pedestrian, 4" base rock, stabilized	400	sf			
	agg paving	400	sf			
29	Extra for sloped grade					
30						
31						
32	PAVING / FLATWORK TOTAL					

ADDITIVE ALTERNATE #6 - ADDITION OF LIVING SHORELINE WORK

Line #	Description	Quantity	Unit	rate	Est. cost	Comments / Subtotal.
33	SITE STRUCTURES / FURNISHINGS					
34						
35						
36	Miscellaneous					
37	Giant timber seat, 6' long	1	ea			
38	Fence, cedar posts, wire mesh, 3'	150	lf			
39						
40	SITE STRUCTURES / FURNISHINGS TOTAL					
41						
42	SIGNAGE					
43						
44	Signage					
45						
46	SIGNAGE TOTAL					
47						
48						
49	PLANTING AND SOIL PREPARATION					
50						
51	Landscape					
52	Import top soil / loam	432	cy			
53	Shoreline planting	23,341	sf			
54	Trees, 24 box	11	ea			
55	Mulch	23,341	sf			
56	120 day Planting Maintenance	1	ls			
57	PLANTING AND SOIL PREPARATION TOTAL					
58						
59	IRRIGATION SYSTEM					
60						
61	Complete irrigation system	11	ea			
62	@ trees					
63						
64	IRRIGATION SYSTEM TOTAL					
65						
66	ELECTRICAL					
67	ELECTRICAL TOTAL					None
68						
69	SUBTOTAL					