

**CITY OF SAUSALITO**  
420 Litho Street, Sausalito, CA 94965

**Addendum No. 3**

Issued **June 15, 2023**

**For**  
**Bridgeway Slide Repair Below 268 Woodward Project**

Page 1 of 2

---

**NOTICE TO ALL PLAN HOLDERS SUBMITTING BIDS FOR THIS WORK:**

You are hereby notified of the following information, changes, clarifications or modifications to the original Contract Documents, Project Manual, Drawings, Specifications and subsequent Addenda. This Addendum shall supersede the original Contract Documents and previous Addenda wherein it contradicts the same and shall take precedence over anything to the contrary therein. All other conditions remain, UNCHANGED.

This Addendum is hereby made a part of the Contract Documents to the same extent as though it were originally included therein.

**RESPONSE TO QUESTIONS**

**1. Question:** The wall profiles are not consistent with size of block. There are rows of half height blocks shown at top and/or bottom of wall. Please confirm that only full height units and caps will be used.

**1. Response:** Only full height blocks and caps will be used.

**2. Questions:** Plan Notes also call out Straw Wattles. No Wattles are included in spec section 11 or shown on plans. Please Clarify.

**2. Response:** Refer to Plan Sheet 6, "Sediment Controls 7. Fiber Rolls". "Fiber Rolls" and "Straw Wattles" are synonymous.

**REVISION:**

**Specifications**

Technical Specifications Section 7.5 Measurement and Payment first paragraph is deleted and replaced as follows:

MSE Retaining Wall (**Bid Item 6c**) shall be measured by the square foot of all blocks shown on plans including buried blocks to support the wall system and caps. The price paid per square foot of MSE Retaining Walls shall include all labor, equipment, materials, purchase and delivery of Versa-Lok standard blocks, reinforcement fabric attached to the walls, concrete, sand and aggregate needed to install the wall system, retaining wall drainage and all incidentals needed to install the retaining wall system as shown on the plans and described herein.

Bridgeway Slide Repair Project  
Addendum No. 3

Technical Specifications Section 11.4 Construction, sixth paragraph is revised as follows:

~~Jute netting complying with Section 21-2.02O(3) of the Standard Specifications shall be installed as final covering on all disturbed ground and secured in place.~~ Refer to Plan Sheet 1, Erosion Control Note 3. Installation of Erosion Control Mats shall be per the manufacturer's recommendations. Fixed aperture netting shall not be allowed.

**END OF ADDENDUM NO. 3**

**Issued By:     City of Sausalito  
                  Andrew Davidson  
                  Senior Engineer**

**ACKNOWLEDGED**

\_\_\_\_\_  
**Bidder's Signature**  
**A signed copy of this addendum is to be submitted as a part of the bid package for the subject project. Failure to do so may subject the Bidder to Disqualification.**