Proposed Duplex Project



429 1/2 Johnson St. Sausalito, CA Date: 5-10-24 Interior Construction Materials:

Flooring: Wood strip floor at 2nd floor areas. Ceramic tile in 2nd floor rest room. Flooring is Terrazzo or concrete slab at basement areas.

Walls and Ceilings: Gypsum board and joint compounds for most rest room and basement walls / ceilings. 2nd floor has open wood ceiling framing above living space.

HVAC and Mech: Forced air furnace / HVAC distributed through fiberglass insulated sheet metal ductwork. HVAC system uses silver duct that is non detect for asbestos. Flue pipe has remnants of hard cast asbestos tape.

Miscellaneous Materials:

Environmental Survey for Renovation

Building Data:

Total Bldg. Area: 1046 Sq. Ft.

Positive ACM at Site:

The hard cast flue tape is friable asbestos.

No asbestos was found in the:

Drywall / Joint Compounds, 9 x 9 floor tiles, concrete, HVAC insulation, glazing putty, or Terrazzo floor. If additional materials are found that do not match the descriptions of the samples analyzed, call for additional testing.

Abatement Specs:

Abatement is required for the flue pipe hard cast tape only. Other materials listed in the sample logs are nonasbestos.

The removal and disposal of fluorescent lamps must follow waste disposal regulations and must be recycled. All older light fixtures should be checked for possible PCB in ballasts.

Exterior Construction Materials:

Foundation: Concrete perimeter foundation, with slab on grade.

Exterior Siding: Exterior wood siding and wood trim. .

Windows: Metal frame windows, with glazing compounds at divided light window units.

Roofing: The main roof is not in the scope of work and not inspected.

General Information:

A survey and report are limited in nature, due to limited ac-

Call for additional site inspections for additional materials that may be uncovered in the demolition process.

Notification to the BAAQMD is required for any structural demolition, regardless of asbestos content. See full report.

MDA

Monte Deignan & Associates

CAC 93-0879 P.O. Box 546 Larkspur, CA 94977 (415) 927-9038



This report may be copied only in its entirety.

May 14, 2024

Mr. Ali Iqbal
City of Sausalito
Public Works
400 Litho Street
Sausalito, CA

Asbestos Survey for Proposed Duplex Vacant Dwelling 429 ½ Johnson Street Sausalito, CA

I. INTRODUCTION

This report presents our limited inspection and bulk sampling for asbestos containing materials ("ACM") at 429 ½ Johnson Street in Sausalito, CA. The inspection was performed on May 10, 2024. The building areas inspected are the interior components at the first and second levels. The primary purpose of this inspection is to identify materials that contain asbestos that must be abated or removed prior to renovation of the structure during a proposed upgrade project. Our scope of work included an asbestos inspection consisting of visual inspection, bulk sampling, laboratory analysis, and the generation of the report findings. The inspection was performed by Mr. Monte Deignan, a Cal/OSHA certified asbestos consultant and AHERA accredited building inspector.

II. REGULATORY OVERVIEW

The following oversight agencies and regulations may affect the implementation of this project as described below:

Federal Agencies

Environmental Protection Agency ("EPA"), National Emission Standards for Hazardous Air Pollutants ("NESHAP") Notification 40 CFR 61 Part M

 Requires notification when removal or renovation involves greater than 160 square feet or 260 linear feet of friable asbestos containing materials

State Agencies/Regulations

Bay Area Air Quality Management District ("BAAQMD")

- Responsible for enforcement of the federal NESHAP regulations
- Requires notification for removal of all friable ACM if exceeding 100 square feet or linear feet
- Requires notification prior to demolition regardless of ACM amounts or presence

California Occupational Safety and Health Administration ("Cal/OSHA")

- Responsible for enforcement of Federal OSHA standards
- Requires friable and non-friable ACM exceeding 100 square feet to be removed by a registered Cal/OSHA asbestos abatement contractor
- Requires that contractors be licensed by the California Contractors State License Board ("CSLB")

AB 3713 Asbestos Notification Law (Connelley Act)

 Requires notification of tenants, employees, and co-owners about the presence and locations of ACM, and the potential health effects

Asbestos Real Estate Disclosure Law

California state law requires the disclosure of ACM presence during real estate transactions.

III. ASBESTOS ANALYSIS PROCEDURES

Sampling Strategy

The objective of bulk sampling was to determine through laboratory analysis whether suspected materials at this site contain asbestos, and if so, what type and concentrations measured in percentages. Prior to the collection of any samples, all building materials were separated into distinct areas of homogeneity. A homogeneous area represents an area delineated by functional and visual similarity. The area may be further defined by its location within the building, or the age of the material.

After homogeneous areas were identified, a sufficient number of samples were collected for submittal to the laboratory for polarized light microscopy ("PLM") analysis. Because asbestos containing materials have compositional variability, it is possible to obtain different results from samples taken from the same materials in the same building. Therefore, a homogeneous sampling area with at least one positive result will result in the entire area being designated as having asbestos containing material ("ACM").

The collection of bulk samples was based on the guidelines established by the EPA for school buildings (Asbestos Hazard Emergency Response Act ("AHERA"), 40 CFR Part 763, EPA, 1987). In addition, the Asbestos in Schools Hazard Abatement Reauthorization Act ("ASHARA") establishes

guidelines for the inspection of commercial facilities. AHERA and ASHARA guidelines were used to insure the most reliable procedures for sample collection and reporting.

Standard sampling tools and procedures were used to obtain samples from the suspected materials. The samples were bagged and submitted to the laboratory under standard chain of custody protocols. Representative sample locations were noted on the floor plans of the building and are referenced on the chain of custody form from the laboratory, Microanalytical Laboratories of Emeryville, California.

Laboratory Analysis

Laboratory analysis was based on polarized light microscopy supplemented by dispersion staining to observe asbestos mineral content. For the purposes of this survey, ACM is defined as any material containing more than 1% asbestos by weight, volume, or point count. For Cal/OSHA purposes, ACCM is defined as any material with greater than 0.1% asbestos.

IV. VISUAL SURVEY FINDINGS AND SAMPLING

On the afternoon of May 10, 2024, the inspection of the property was performed. The age of the building and the use of asbestos containing materials are usually related. Most buildings from the 1960's used many asbestos containing material (ACM) for components such as flooring, drywall, roofing, insulation, etc. The inspection was limited to the rooms or scope of work areas shown on the floor plan included with this report. Arrange for additional testing if other areas are to be disturbed or renovated.

Walls and Structural Components

The house consists of exterior and interior walls of wood frame and wood frame roof structure, on a concrete perimeter foundation. The interior walls are mostly wood paneled, with limited areas of drywall. The windows in the building are mostly metal frame / sash units, with glazing compounds on the larger multi light windows.

The ceilings at most areas are drywall or wood siding materials.

The floor plan indicates the locations and samples collected of the wall and ceiling materials.

Exterior and Roofing Components

The office exterior and roofing materials were not tested for this inspection. If the roofing is disturbed or replaced, arrange for additional inspections / sampling.

Flooring Components

The building flooring components are Terrazzo and exposed concrete for first floor areas. The second floor uses wood strip flooring. Limited areas of ceramic tile are used in the rest room areas. A small amount of 9 x 9 vinyl tile was found at the second floor bathroom.

Mechanical Systems, Utilities, etc.

This category includes the HVAC, hot water, etc. Each of these systems uses different insulation materials, which are typically suspect for containing asbestos. The building HVAC system consists of forced air furnace. And water heater in the garage. The HVAC ducts that extend through the interstitial or above ceiling spaces uses fiberglass for insulation. The ducts use a silver colored fabric duct tape at sheet metal ductwork. The flue pipes use a hard cast tape and joins and seams in the sheet metal pipes. Most of the hard cast tape is missing but about 1 square foot remains in poor condition. The hard cast tape is classified as friable.

Supplemental Environmental Concerns

The scope of this inspection and report are primarily limited to asbestos containing materials in the buildings. There are however additional concerns that should be addressed prior to and during the renovation of the buildings. The owners of the property should consider obtaining additional advice from qualified professionals regarding the presence of additional hazards. The following are examples of what may be found:

- The lighting in some areas of the building possibly use fluorescent fixtures. These lights use lamps that contain mercury. The ballasts may also contain PCB oils. The lamps shall be recycled if removed or replaced. The labels on ballasts shall be checked for the "No PCB" label at the time of any future fixture replacement.
- Any demolition, drilling, or disturbance of the concrete slab and foundations should follow the Cal / OSHA regulations for Respirable Crystalline Silica found in 8 CCR 1532.3. Any work that generates dust from concrete must use engineering controls, work methods, and PPE to limit worker exposure.

Sampling of Building Materials

Samples were collected from twenty-three different building materials and analyzed for asbestos. Since no other suspect materials could be found, the sampling was considered complete. All of the samples were catalogued as to location, condition, and submitted for PLM analysis. The samples were hand-delivered to the laboratory using our standard chain of custody protocols on the morning of May 11, 2024

The description of the materials, locations and quantity are listed on the chain of custody forms and floor plans. The titles for the various spaces in the house were assumptions based on the apparent use of the space. Photographs were also taken to document the location and conditions of some of the materials. Copies of the floor plan and chain of custody forms are attached with this report.

V. CONCLUSIONS

Based on the visual inspection, sampling and laboratory analysis, the following results are noted:

- The hard cast tape on the HVAC flue pipes contain 60% asbestos.
- The 9 x 9 vinyl tile was non detect for asbestos.
- The HVAC duct insulation and silver duct tape do not contain asbestos.
- The drywall and joint compounds do not contain asbestos.
- The ceramic and grout tiles do not contain asbestos.
- The concrete / Terrazzo flooring does not contain asbestos.
- The concrete block/ CMU at the basement does not contain asbestos.
- The exterior glazing compound does not contain asbestos.

RECOMMENDATIONS Based on the visual inspection, sampling and laboratory analysis conducted, the following recommendations apply to the materials found on this site:

- The hard cast tape on the flue pipes for the furnace and water heater is in poor condition and must be abated prior to demolition or disturbance. The abatement must follow Cal / OSHA 8 CCR Section 1529 regulations for friable thermal system insulation materials. Wet methods, containment, performed by qualified asbestos contractors will be required
- 2. The ceramic tile / grout, duct tape, concrete, 9 x 9 vinyl tile, Terrazzo flooring, drywall and joint tape compounds, and glazing compound materials were non detect at the locations sampled and no abatement regulations apply to these materials. If other materials are uncovered during the renovation project, arrange for additional inspections.
- 3. The fluorescent lighting tubes and bulbs must be recycled due to mercury content, in fixtures that are removed. Ballasts shall be check for possible PCB content.
- 4. Notification to the BAAQMD must be made for structural demolition or removal of a load bearing members. This is separate to any asbestos related notifications for abatement operations.

Any chemicals to be used on the project must be accompanied by a Safety Data Sheet ("SDS"). Compliance with this section is not required by asbestos regulations.

VI. LIMITATIONS OF LIABILITY

The work and resulting recommendations for this survey are in accordance with generally accepted building survey practices and the AHERA protocols for asbestos inspections. The report generators provide no other guarantees, either expressed or implied. Conclusions and recommendations presented in issued reports are qualitative judgments based on the prevailing regulations affecting the scope of this work at the time of the inspection of the particular building(s). The scope of work was limited to the visible and accessible parts of the building, limited sampling analysis, and data review. The client recognizes that site conditions or access may vary from those encountered at the time of the inspection, and that changing conditions may cause us to alter our recommendations. We have attempted to view as much of the building as possible, without opening hidden areas, removing existing drywall, or damaging existing property. If conditions or situations occur that expose these non-inspected areas, we will be glad to continue our inspection at that time for those locations.

This report is for the express use of the client for whom it was prepared, and is not intended for use by third parties. The authors of this report will not be responsible for interpretation or use by third parties of any of the information contained in this report. The building survey for asbestos is intended to provide an initial assessment of asbestos containing material at specific locations, and may not be valid at other locations or for other unique materials. Additional site evaluations could result in information that would lead us to revise our conclusions and recommendations. If any doubts exist, call for additional inspections or testing.

Respectfully submitted.

Mart Dignan

Monte Deignan CAC 93-0879

Monte Deignan & Associates Certified Asbestos Consultant P.O. Box 546 • Larkpsur, CA 94977 • (415) 927-9038

Interior Construction Materials Proposed City Housing 4291/2 Johnson Street Sausalito, CA



The second level ceiling is wood beams and wood planks.

The ceiling at the lower floor is mostly gypsum board and compounds.

The roof and exterior materials were not included in the survey.

The flooring in most areas is wood strip over wood framing at the second level. The basement is mostly Terrazzo or concrete slab on grade. No asbestos was detected in floor samples.


The partition walls in the building are wood framing in all areas. Most of the second level walls use wood paneling. The lower levels use gypsum board finished with joint tape compounds.

The gypsum board, joint compounds, are non detect for asbestos.

Proposed City Housing

4291/2 Johnson Street Sausalito, CA

May 10, 2024 Scope of Work for Abatement & Demolition






The first floor main room uses Terrazzo concrete flooring as shown in Photo 2. The walls and ceilings of the lower level are gypsum board. Drywall joint tape compounds are used to finish the drywall surfaces. The shower in the bathroom uses ceramic tile and grout for the wall surfaces. The foundation at the lower level is a concrete perimeter system, with limited areas of concrete block or CMU in the garage storage area.

Based on the PLM sampling and laboratory analysis the drywall, ceramic tile, Terrazzo, concrete, and duct tape samples were non detect for asbestos content.

The gas fired furnace and water heater is located in the garage area of the basement. The forced air furnace uses sheet metal duct work, sealed with a silver colored duct tape at pipe seams. Fiberglass is used for insulation on the duct work in the basement / crawl space. The flue pipe for the furnace and water heater is galvanized sheet metal. A hard cast tape is used at the joint between the flue pipe sections. Much of the hard cast tape is missing, but about 1 square foot remains. The hard cast tape contains 60% asbestos and is classified as friable. The residual hard cast tape must be abated by a qualified asbestos abatement contractor prior to removal of disturbance. The red circles in Photo 3 show some of the hard cast tape locations.



Proposed Duplex

429 1/2 **Johnson** Sausalito, CA

Asbestos Survey First Floor

May 10, 2024



MDA

Monte Deignan & Associates Certified Asbestos Consultants Larkspur, CA

7-1115/61 16'-114 5-5510 3'-61/2" BALCONY **CSD-22** Glazing DECK 0 CSD-03 Drywall **CSD-08** CSD-05 Grout Cer. Tile CSD-02 CSD-07 Drywall 9x Vin. Tile CSD-23 Glazing CSD-01 **Drywall** (V208) **EXISTING SECOND STORY** CSD-06 **CSD-04** Cer. Tile **Drywall**

Proposed Duplex

429.5 Johnson Sausalito, CA

Asbestos Survey

May 10, 2024



MDA

Monte Deignan & Associates Certified Asbestos Consultants Larkspur, CA

BULK ASBESTOS ANALYSIS - POLARIZED LIGHT MICROSCOPY (PLM)



1084 Monte Deignan Monte Deignan & Associates P.O. Box 546 Larkspur, CA 94977 PROJECT:

429 1/2 JOHNSON STREET SAUSALITO, CA Micro Log In

314853

Total Samples 23

Date Sampled 05/10/2024

Date Received

05/11/2024

Date Analyzed 05/11/2024

SAMPLE IDENTIFICATION

ASBESTOS QUANTITY (AREA %) / TYPES / LAYERS

If absent, ND Is Reported (No Asbestos Detected)

DOMINANT OTHER MATERIALS

Client #:	CSD-01		10 % CELLULOSE
Micro #: 314853-01 DRYWALL & JOINT CO 1ST FLOOR ENTRY	Analyst: AF AF	DRYWALL: ND JOINT COMPOUND: ND TAPE / PAINT: ND MESH: ND	3 % FIBROUS GLASS NFM: 'GYPSUM' (CALGIUM SULFATE), CARBONATE.
Client #: Micro #: 314853-02 DRYWALL & JOINT CO STAIRWELL @ 2ND	CSD-02 Analyst: AF MPOUND	DRYWALL: ND JOINT COMPOUND: ND TAPE / PAINT: ND	10 % CELLULOSE NFM: 'GYPSUM' (CALCIUM SULFATE), CARBONATE.
Client #: Micro #: 314853-03 DRYWALL & JOINT CO REST ROOM @ 2ND	CSD-03 Analyst: AF MPOUND	DRYWALL: ND JOINT COMPOUND: ND TAPE / PAINT: ND	10 % CELLULOSE NFM: 'GYPSUM' (CALCIUM SULFATE), CARBONATE.
Client #: Micro #: 314853-04 DRYWALL & JOINT CO REST ROOM @ 2ND	CSD-04 Analyst: AF MPOUND	DRYWALL: ND JOINT COMPOUND: ND TAPE / PAINT: ND	10 % CELLULOSE NFM: 'GYPSUM' (CALCIUM SULFATE), CARBONATE.
Client #: Micro #: 314853-05 3X3 CERAMIC TILE REST ROOM @ 2ND	CSD-05 Analyst: AF	CERAMIC TILE: ND GLUE (WHITE): ND GLUE (GRAY): ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER

Technical Supervisor:

Baojia Ke, Ph.D.

5/11/2024 Date Reported

NVLAP Lab Code 101872-0 (TESTING). Analyses use Polarized Light Microscopy (PLM), Micro Analytical SOP PLM-101. Basic techniques follow EPA – Appendix E to Subpart E of 40 CFR Part 763; Interim Method for the Determination of Asbestos in Bulk Insulation Samples" (originally published 1982), and EPA-600/R93-116 (1993). The 1993 method covers all types of bulk materials and is based on the 1982 Method, with improved analytical techniques for layered samples as required for NESHAP compliance. Asbestos is quantified by calibrated visual estimation. Detection limit is material dependent. Detection of asbestos traces (much less than 1%) may not be reliable or reproducible by PLM. Weight % cannot be determined by PLM. Asbestos with diameter below ~1 µm may not be detected by PLM. Absence of asbestos in dust, debris, and some compact materials, including floor tiles, cannot be conclusively established by PLM, and should be confirmed by Transmission Electron Microscopy (TEM).Interferences may prevent detection of small asbestos fibers, and hinder determination of some optical properties. Tremolite-asbestos are actinoite-asbestos may be indistinguishable by PLM from some similar, non-regulated amphiboles (e.g. the "Libby Amphiboles" richterite and winchife), and should be confirmed by TEM. The lower quantitation limit (reporting limit) of PLM estimation; by TLM or the lower quantitation limit (reporting limit) of PLM estimation; by TLM or the Cal-OSHA definition of asbestos-containing construction material is 0.1% asbestos-containing construction material is 1.0.1% asbestos-containing construction material is 0.1% asbestos-containing construction material is 0.1% asbestos

BULK ASBESTOS ANALYSIS - POLARIZED LIGHT MICROSCOPY (PLM)



1084 Monte Deignan Monte Deignan & Associates P.O. Box 546 Larkspur, CA 94977

PROJECT:

429 1/2 JOHNSON STREET SAUSALITO, CA

Micro Log In

314853

Total Samples

23

Date Sampled

05/10/2024

Date Received

05/11/2024

Date Analyzed

05/11/2024

SAMPLE IDENTIFICATION

ASBESTOS QUANTITY (AREA %) / TYPES / LAYERS

If absent, ND Is Reported (No Asbestos Detected)

DOMINANT OTHER MATERIALS

		If absent, ND is Reported (No Asbestos Detected)	
Client #:	CSD-06		5 % CELLULOSE
4X4 CERA	14853-06 Analyst: AF AMIC TILE OM @ 2ND	CERAMIC TILE: ND GLUE (WHITE): ND RESIDUAL COMPOUND: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER
Client #:	CSD-07		
Micro #: 3 9X9 VINYI REST RO	14853-07 Analyst: AF AF L TILE, BROWN OM @ 2ND	VINYL TILE: ND MASTIC (BEIGE): ND	NFM: SYNTHETIC MATERIAL, CARBONATE, ADHESIVE.
Client #:	CSD-08		
Micro #: 3: FLOOR TI REST ROO	14853-08 Analyst: AF ILE GROUT, GRAY OM @ 2ND	GROUT: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER
Client #:	CSD-09		10 % CELLULOSE
_	14853-09 Analyst: AF L & JOINT COMPOUND NT	DRYWALL: ND JOINT COMPOUND: ND TAPE / PAINT: ND	NFM: 'GYPSUM' (CALCIUM SULFATE), CARBONATE,
Client #:	CSD-10		10 % CELLULOSE
	14853-10 Analyst: AF L & JOINT COMPOUND OM @ BASEMENT	DRYWALL: ND JOINT COMPOUND: ND TAPE / PAINT: ND	NFM: 'GYPSUM' (CALCIUM SULFATE), CARBONATE.

Technical Supervisor:

Baojia Ke, Ph.D.

5/11/2024 Date Reported

NVLAP Lab Code 101872-0 (TESTING). Analyses use Polarized Light Microscopy (PLM), Micro Analytical SOP PLM-101. Basic techniques follow EPA – Appendix E to Subpart E of 40 CFR Part 763; Interim Method for the Determination of Asbestos in Bulk Insulation Samples" (originally published 1982), and EPA-600/R93-116 (1993). The 1993 method covers all types of bulk materials and is based on the 1982 Method, with improved analytical techniques for layered samples as required for NESHAP compliance. Asbestos is quantified by calibrated visual estimation. Detection limit is material dependent. Detection of asbestos traces (much less than 1%) may not be reliable or reproducible by PLM. Weight % cannot be determined by PLM. Asbestos with diameter below ~1 µm may not be detected by PLM. Absence of asbestos in dust, debris, and some compact materials, including floor titles, cannot be conclusively established by PLM and should be confirmed by Transmission Electron Microscopy (TEM). Interferences may prevent detection of small asbestos fibers, and hinder determination of some optical properties. Tremolite-asbestos are actinoite-asbestos may be indistinguishable by PLM from some similar, non-regulated amphiboles (e.g. the "Libby Amphiboles" richterite and winchife), and should be confirmed by TEM. The lower quantitation limit (reporting limit) of PLM estimation is 1%. The Cal-OSHA definition of asbestos-containing construction material is 0.1% asbestos; however, reliable determination of asbestos percent at this level cannot be done by PLM estimation; PLM Point Counting or TEM weight percent analysis are recommended. Only dominant non-asbestos materials (fibrous and non-fibrous) are listed. This analysis shall not be construed as conclusive for the presence of any reported materials other than asbestos, or for the absence of any non-asbestos material. Common interferences include, but are not limited to: cellulose, fibrous glass, other man-made vitreous fibers, synthetic fibers, elongate fragments of calcium sulfate, taic, woll

DY

BULK ASBESTOS ANALYSIS - POLARIZED LIGHT MICROSCOPY (PLM)



1084 Monte Deignan Monte Deignan & Associates P.O. Box 546 Larkspur, CA 94977

PROJECT:

429 1/2 JOHNSON STREET SAUSALITO, CA

Micro Log In

314853

Total Samples

23

Date Sampled Date Received 05/10/2024

05/11/2024

Date Analyzed

05/11/2024

SAMPLE IDENTIFICATION

ASBESTOS QUANTITY (AREA %) / TYPES / LAYERS

If absent, ND is Reported (No Asbestos Detected)

DOMINANT OTHER MATERIALS

Client #:	CSD-11		10 % CELLULOSE
Micro #: 314853-1 DRYWALL & JOINT REST ROOM @ BAS	COMPOUND	DRYWALL: ND JOINT COMPOUND: ND TAPE / PAINT: ND	NFM: 'GYPSUM' (CALCIUM SULFATE), CARBONATE.
Client #:	CSD-12		55 % CELLULOSE
Micro #: 314853-12 DUCT TAPE, SILVE HVAC DUCTS		DUCT TAPE: ND	NFM: BINDER, OTHER, MISCELLANEOUS.
Client #:	CSD-13		10 % CELLULOSE
Micro #: 314853-10 HARD CAST TAPE, FLUE PIPES	_	CAST TAPE: 60% CHRYSOTILE ASBESTOS	NFM: BINDER, OTHER, MISCELLANEOUS.
Client #:	CSD-14		
Micro #: 314853-14 FLEXIBLE CONNEC HVAC RETURN DUC	TOR	CONNECTOR MATERIAL: ND	65 % SYNTHETIC FIBERS NFM: BINDER, OTHER, MISCELLANEOUS.
Client #:	CSD-15		
Micro #: 314853-15 3X3 CERAMIC TILE RESTROOM @ BAS	-	CERAMIC TILE: ND GLUE (GRAY): ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER

Technical Supervisor:

Baojia Ke, Ph.D.

5/11/2024 Date Reported

NVLAP Lab Code 101872-0 (TESTING). Analyses use Polarized Light Microscopy (PLM), Micro Analytical SOP PLM-101. Basic techniques follow EPA – Appendix E to Subpart E of 40 CFR Part 763; Interim Method for the Determination of Asbestos in Bulk Insulation Samples" (originally published 1982), and EPA-600/R93-116 (1993). The 1993 method covers all types of bulk materials and is based on the 1982 Method, with improved analytical techniques for layered samples as required for NESHAP compliance. Asbestos is quantified by calibrated visual estimation. Detection limit is material dependent. Detection of asbestos traces (much less than 1%) may not be reliable or reproducible by PLM. Weight % cannot be determined by PLM. Asbestos with diameter below ~1 µm may not be detected by PLM. Absence of asbestos in dust, debris, and some compact materials, including floor tiles, cannot be conclusively established by PLM, and should be confirmed by Transmission Electron Microscopy (TEM).Interferences may prevent detection of small asbestos inderence of asbestos expected by PLM from some similar, non-regulated amphiboles (e.g. the "Libby Amphiboles" richterite and winchile), and should be confirmed by TEM. The lower quantitation limit (reporting limit) of PLM estimation is 1%. The Cal-OSHA definition of asbestos-containing construction material is 0.1% asbestos; however, reliable determination of asbestos percent at this level cannot be done by PLM estimation; PLM Point Counting or TEM weight percent analysis are recommended. Only dominant non-asbestos materials (fibrous and non-fibrous) are listed. This analysis shall not be construed as conclusive for the presence of any reported materials other han asbestos, or for the absence of any non-asbestos material. Common interferences include, but are not limited to: cellulose, fibrous glass, other man-made vitreous fibers, synthetic fibers, elongate fragments of calcium sulfate, talc, wollastonite, animal hair, and other miscellaneous elongate particles. Sample heterogeneity is indicate

SOV

BULK ASBESTOS ANALYSIS - POLARIZED LIGHT MICROSCOPY (PLM)



1084 Monte Deignan Monte Deignan & Associates P.O. Box 546 Larkspur, CA 94977

PROJECT:

429 1/2 JOHNSON STREET SAUSALITO, CA

Micro Log In

314853

Total Samples

23

Date Sampled

05/10/2024

Date Received

05/11/2024

Date Analyzed

05/11/2024

SAMPLE IDENTIFICATION

ASBESTOS QUANTITY (AREA %) / TYPES / LAYERS

If absent, ND is Reported (No Asbestos Detected)

DOMINANT OTHER MATERIALS

Client #:	CSD-16		
TILE GRO	114853-16 Analyst: AF DUT, GRAY OM @ BASEMENT	GROUT: ND RESIDUAL CAULK: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER
Client #:	CSD-17		
	14853-17 Analyst: AF ZO FLOOR, WHITE NT	TERRAZZO: ND CONCRETE: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER
Client #:	CSD-18		
TERRAZZ	.14853-18 Analyst: AF 20 FLOOR, WHITE DM @ BASEMENT	TERRAZZO: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER
Client #:	CSD-19		
TERRAZZ	14853-19 Analyst: AF ZO FLOOR, WHITE DM @ BASEMENT	TERRAZZO: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER
Client #:	CSD-10		
Micro #: 3	14853-20 Analyst: AF TE, GRAY NT	CONCRETE: ND PAINT: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER

Technical Supervisor:

Baojia Ke, Ph.D.

5/11/2024 Date Reported

er: NVLAP Lab Code 101872-0 (TESTING). Analyses use Polarized Light Microscopy (PLM), Micro Analytical SOP PLM-101, Basic techniques follow EPA – Appendix E to Subpart E of 40 CFR Part 763; Interim Method for the Determination of Asbestos in Bulk Insulation Samples" (originally published 1982), and EPA-600/R93-116 (1993). The 1993 method covers all types of bulk materials and is based on the 1982 Method, with improved analytical techniques for layered samples as required for NESHAP compliance. Asbestos is quantified by calibrated visual estimation. Detection limit is material dependent. Detection of asbestos traces (much less than 1%) may not be reliable or reproducible by PLM. Asbestos with diameter below ~1 µm may not be detected by PLM. Asbestos in dusf, debris, and some compact materials, including floor tiles, cannot be conclusively established by PLM, and should be confirmed by Transmission Electron Microscopy (TEM). Interferences may prevent detection of some optical properties. Tremolite-asbestos or actinolite- asbestos may be indistinguishable by PLM from some similar, non-regulated amphiboles (e.g., the "Libby Amphiboles" inchterite and winchife), and should be confirmed by TEM. The lower quantitation limit (reporting limit) of PLM estimation is 1%. The Cal-OSHA definition of rothe presence of any reported materials other than asbestos, however, reliable determination of asbestos percent at this level cannot be done by PLM estimation; PLM Point Counting or TEM weight percent analysis are recommended. Only dominant non-asbestos materials (fibrous and non-fibrous) are listed. This analysis shall not be construed as conclusive for the presence of any reported materials other than asbestos, or for the absence of any non-asbestos material. Common interferences include, but are not limited to: cellulose, fibrous glass, other man-made vitreous fibers, synthetic fibers, elongate fragments of calcium sulfate, taic, wollation, electronic analysis are recontained by listing more than one distinct layer or material o

BULK ASBESTOS ANALYSIS - POLARIZED LIGHT MICROSCOPY (PLM)



1084 Monte Deignan Monte Deignan & Associates P.O. Box 546 Larkspur, CA 94977 PROJECT:

429 1/2 JOHNSON STREET SAUSALITO, CA Micro Log In

314853

Total Samples

s 23

05/10/2024

Date Sampled
Date Received

05/11/2024

Date Analyzed

05/11/2024

SAMPLE IDENTIFICATION

ASBESTOS QUANTITY (AREA %) / TYPES / LAYERS

if absent, ND is Reported (No Asbestos Detected)

DOMINANT OTHER MATERIALS

Client #:	CSD-11		
Micro #: 314853-21 CONCRETE BLOCK, BASEMENT	•	CONCRETE: ND PAINT: ND	NFM: ROCK FRAGMENTS, CARBONATE, BINDER
Client #:	CSD-12		
Micro #: 314853-22 GLAZING PUTTY, GI WINDOW @ 2ND FLI	RAY	PUTTY: ND	NFM: CARBONATE, MISC, PARTICLES
Client #:	CSD-13		
Micro #: 314853-23 GLAZING PUTTY, GI WINDOW @ 2ND FLI	RAY	PUTTY: ND	NFM: CARBONATE, MISC. PARTICLES

Technical Supervisor:

5/11/2024

Baojia Ke, Ph.D. Date Reported

NVLAP Lab Code 101872-0 (TESTING). Analyses use Polarized Light Microscopy (PLM), Micro Analytical SOP PLM-101. Basic techniques follow EPA – Appendix E to Subpart E of 40 CFR Part 763; Interim Method for the Determination of Asbestos in Bulk Insulation Samples" (originally published 1982), and EPA-800/R93-116 (1993). The 1993 method covers all types of bulk materials and is based on the 1982 Method, with improved analytical techniques for layered samples as required for NESHAP compliance. Asbestos is quantified by calibrated visual estimation. Detection limit is material dependent. Detection of asbestos traces (much less than 1%) may not be reliable or reproducible by PLM. Weight % cannot be determined by PLM. Asbestos with diameter below ~1 µm may not be detected by PLM. Absence of asbestos in dust, debris, and some compact materials, including floor tiles, cannot be conclusively established by PLM, and should be confirmed by Transmission Electron Microscopy (TEM). Interferences may prevent detection of small asbestos fibers, and hinder determination of some optical properties. Tremolite-asbestos or actinolite-asbestos may be indistinguishable by PLM from some similar, non-regulated amphiboles (e.g. the "Libby Amphiboles" richterite and winchile), and should be confirmed by TEM. The lower quantitation limit (reporting limit) of PLM estimation is 1%. The Cal-OSHA definition of asbestos-containing construction material is 0.1% asbestos-showever, reliable determination of asbestos percent at this level cannot be done by PLM estimation; PLM Point Counting or TEM weight percent analysis are recommended. Only dominant non-asbestos materials (fibrous and non-fibrous) are listed. This analysis shall not be construed as conclusive for the presence of any reported materials other than asbestos, or for the absence of any non-asbestos material. Common interferences include, but are not limited to: cellulose, fibrous glass, other man-made vitreous fibers, synthetic fibers, elongate fragments of calcium sulfate, talc, woll



Bulk Sample Log & Laboratory Request Form

Client #: Log In #:

Mc	nte Deignan	
&	Associates	

P.O. Box 546 Larkspur, CA 94977

Tel (415) 927-9038

Client: City of Sausalito

400 Litho Street Sausalito, CA

City, State: Project Site: 4291/2 Johnson Street

Sausalito, CA

Collected By: MD Date: 05-10-24 Analysis Requested: PLM Rush 24 Hr. TEM Pb 3-5 Day Misc. Other

	The state of the s			
Sample	Sample Description	Sample Location	Notes	Lab#
CSD -01	DEYLYALL & JOINT COMPOUND			
CSD -OZ	try Vale & JOINT COMPOUNT			
CSD	DRYIVALL & JOINT COMPOUNT			
C50 -04	TRYWALL & JOINT COMPOUND	PEST PAON 6 2ND		
CSP -05	3×3 CEPAMIC TILE	PEST PROM @ 2ND		
C50 -06		REST ROOM & 2ND		
esp -07	9x9 VINYLTILE, EPOWN	PEST ROOM & CND		
CSP - 08	FLOOR TIVE GROUT, GRAY	PEST PROME 2ND		
CSP	trywal & JoINT COMPOUND			
-10	DEYMALL & JOINT COMPOUND	PUST ROOM @ BASENENT		

Laboratory Name / Address:

Microanalytical Laboratory 5900 Hollis Street Emeryville, CA 94608

Transfered To: Sowpe Transfered By:

Bulk Sample Log & Laboratory Request Form

Client #:

Log In #:

Mc	nte	Deignan
&	Ass	ociates

P.O. Box 546 Larkspur, CA 94977

Tel (415) 927-9038

Client: City of Sausalito 400 Litho Street

City, State: Sausalito, CA

Project Site: 4291/2 Johnson Street

Sausalito, CA

Collected By: MD

Date: 05-10-24

Misc. Other

Sample	Sample Description	Sample Location	Notes	Lab#
CSD -11	TRYIVAL & JOINT COMPORNT	POST FROM STATULANT		
CSD -IZ	THE TAPE, SILVER	HVAC DISTS		
CSP	HARD CAST TAPE, GRAY	FLUE PIPES		
CSD	PLEXIBLE CONNECTOR	HVAC RETURN DOCT		
CSP -15	3×3 CERAMIC TILE	POST ROOM & BASEMT.		
CSD	TIVEGROUT, GRAY	PEST FROM & BASEMENT		
CSD -17	TERRAZZO FLOOR, WHITE	PACEMENT		
CSD -18	TERRAZZO FLOOR, WHITE	POST PROME BASEMENT		
CSD -19	TEPPAZZO FLOOP, WHITE	PES FROM & EASEMENT	-	
CSD -20	CONCRETE, GRAY	EASEMENT		

Laboratory Name / Address:

Microanalytical Laboratory 5900 Hollis Street Emeryville, CA 94608

Released By Page 2 Of 3 Transfered To:

Bulk Sample Log & Laboratory Request Form

Client #:

Log In #:

Monte Deigna	n
& Associates	

P.O. Box 546 Larkspur, CA 94977

Tel (415) 927-9038

Client: City of Sausalito 400 Litho Street

City, State: Sausalito, CA

Project Site: 4291/2 Johnson Street

Sausalito, CA

Collected By: MD

Date: 05-10-24

Pb 3-5 Day Other Other

Sample	Sample Description	Sample Location	Notes	Lab#
CSD -ZI	CONCRETE BLOCK, CMU	BASEMENT		
C30 -22	GLAZING PUTTY, GPAY	WINDOW @ 2ND FLE		
CSD -23	CONCRETE BLOCK, CMU GLAZING PUTTY, GPAY GLAZING PUTTY, GPAY	VINDOW & ENDRIE		

_aboratory Name / Address :

Microanalytical Laboratory 5900 Hollis Street Emeryville, CA 94608

0:30 PM

Released By: Mat Page 3. Of 3

Transfered To: SAUPE TROP

Received By:

30